



NATIONAL INSTITUTE OF UNANI MEDICINE

Kottigepalya, Magadi Main Road, Bangalore – 560 091
(An autonomous body under Ministry of AYUSH, Govt. of India)
(Accredited to NABH)



Tel: 080-23584260

Fax: 080-23584180

F. No. 17-5/2020-21/Admn/NIUM

808

Date: 21.10.2020

To,

Sub: To submit the Quotation for Civil works at NIUM – reg:

Sir,

With reference to the subject cited above, and directed to inform that civil works to be carried out at this Institute as specification detailed below.

1 Director Chamber Bathroom

Sl No	Description of Item	Unit	Quantity	Rate	Amount
1	Removing and disposal of existing floor tiles and refixing new 15x15 size 10mm thick tiles as including charges of M sand, Cement adhesive, labor, machinery, chemical washing etc. as per specifications.	Sft	100		
2	Removing and disposal of existing old commode and refixing of new Single piece or Wall hanging western Cera commode (basic series) including fixing of health fauset, one no of tap, including labor etc. as per specification.	No	1		
3	Providing and fixing of CERA wash basin including its all fittings, labor etc.	No	1		
4	Providing and fixing of good quality S S Towel railing	No	1		
5	Providing and fixing of 2x3 sized framed mirror.	No	1		

2 Foundation protection and Drainage Wall Construction

Sl No	Description of Item	Unit	Quantity	Rate	Amount
1	Earth excavation for foundation of Compound wall in ordinary soil including Charges of Labor, dressing the bottom, etc. as per specification.	CFT	116		
2	Bed concrete providing and laying in position plain cement concrete of nominal mix 1:4:8 using 40mm and down size graded granite metal machine mixed, concrete laid in layers not exceeding 15 cms thick, well compacted, in foundation including cost of all materials, labor, HOM of machinery, curing completed as per specifications.	CFT	8.7		
3	Providing and constructing size stone masonry wall with cement mortar 1:6 in 1.5 feet width courses, bond stones at two m. apart in each course and pointing two sides including cost of materials, labor, curing complete as per specifications.	CFT	78.3		
4	Providing and laying in position plain cement concrete for Plinth (Foundation protection) of mix 1:2:4 using 20mm and down size graded granite metal Machine mixed, concrete thickness 10 cms. Well compacted, and neat finishing with 1:4 proportion mortar including cost of all materials, labor, HOM of machinery, curing complete as per specifications.	CFT	26.24		

3 Civil Works Opposite Guest House

Sl No	Description of Item	Unit	Quantity	Rate	Amount
1	Providing and laying of 1:2:3 proportioned concrete with slope and neat finished for Ramp and Relaying of existing cobble stones (some portion) opposite to Guest house including all material labor etc.	CFT	10.5		

- The area may be inspected before submitting the estimate to the above work.
- The firm may mention the GST No. properly and time required for completion of the above work and may mention the taxes separately if applicable.
- Any sort of damages caused during the work the firm is wholly & solely responsible.
- For delay in completing the work following penalty shall be imposed.
 - For delay of five days 5% of the billed amount.
 - For delay of 6-10 days 10% of the billed amount.
 - For delay of 11-15 days 15% of the billed amount.
 - For delay of 16-20 days 20% of the billed amount and there after no payment will be released.
- If any dispute arises the decision of Director, NIUM is final and binding.
- The quotation may be submitted in a sealed cover by super scribing as "Civil and Bathroom works at NIUM" and submit the same to this office by hand or post on or before 04.11.2020.

Yours faithfully,

(Nadeem A Siddiqui)
Administrative Officer

Distribution:

- Dr. Malik Itrat, Website I/c to upload the above estimate in the Institute website.
- Guard file.